

## **UNCHA LAKE PERLITE DEPOSIT**

**NTS MAP 93F/13E**

**GEOLOGICAL SURVEY BRANCH**  
MAY 2004

27,964

**Innovative Energy Inc.**

21664 Monahan Court  
Langley BC Canada V3A 8N1  
Ph: (604) 532-6463  
FAX: (604) 532-6494  
Email: [hoppelt@telus.net](mailto:hoppelt@telus.net)

❖ **REPORT DONE BY HAROLD R OPPELT**

## **EXECUTIVE SUMMARY**

The Uncha Lake Perlite deposit is located 25 miles south of the Town of Burns Lake in north central British Columbia, 600 miles northwest of Vancouver. The deposit occurs on the northwest slope of Dayeezcha Mountain. The deposit is accessible year-round by well maintained roads. Eight mineral claims, known as the 'Day' Claims, cover the Uncha Lake deposit. Topography in the area is gently rolling terrain covered with glacial till and thick forest cover. The Uncha Lake Perlite deposit is an early stage exploration prospect.

The Uncha Lake Perlite layers occur within rhyolite flows of the Eocene aged Oosta Lake Group overlying sedimentary and volcanics of the Jurassic Hazelton Formation. The Oosta Lake Group consists mainly of felsic volcanic rocks and coarse clastic layers.

The Uncha Lake Perlite Prospect is considered to be of comparable quality and physical properties to the Frenier Deposit near Clinton, BC. The Frenier Deposit was a commercial deposit mined from 1983 through 1985 but due to access problems the mining was halted. The Francois Lake Perlite deposit, 14 miles south of Burns Lake, was formerly mined from 1949 to 1953 by Western Gypsum Products.

The Uncha Lake perlite has been tested to expand moderately well and exhibit perlitic structure in outcrop. Water loss on heating has been calculated to be approximately 3.2% on samples tested by CANMET from the Uncha Lake prospect area. The perlite layers ranges from 7.6 metres to 23 metres thick and can be traced in outcrops and from previous trenching for over 850 metres along the mountainside. It is considered to occur in significant quantities to warrant further exploration and potential mining. Preliminary resource estimate may be as much as 4 million tonnes of perlite in place for the Uncha Lake deposit. Further exploration by mapping, trenching, and drilling will provide better estimate of reserves and mineability.

## UNCHA LAKE PERLITE DEPOSIT

### 1. Introduction

**Perlite** is a term applied to any hydrated volcanic glass of rhyolitic composition which when heated to temperatures greater than 510°C will expand to form a white, porous, lightweight material. In its expanded form perlite is used as an insulating aggregate in plaster and concrete, in horticultural applications and as a filtering agent. Deposits are restricted to volcanic belts ranging in age from Tertiary to Quaternary. At present, all perlite consumed in British Columbia is imported from the United States.




Figure 1: Perlite occurrences in British Columbia.

## **2. Location and Access**

The Uncha Lake Perlite Deposit is located in the Omineca Mining Division within the 93F/13E NTS map sheet. The Uncha Lake Perlite Deposit is located on the northwest slopes of Dayeezcha Mountain 25 miles south of the town of Burns Lake, British Columbia (Figure 2). The deposit is reached by taking the all-weather Highway 35 to the ferry terminal at Francois Lake, crossing the lake to the South Bank terminal and continuing on the BC Forest Service Road for approximately 12 miles to the Dayeezcha Mountain area. The Day Claims are located 4.5 miles directly south of Uncha Lake. The roads in the area are well maintained as logging companies are very active in the area. There is road access directly into the property (Figure 3).

Most of the area is very lightly settled, with some small towns along major rivers; major settlements include Burns Lake to the north, Houston, 55 miles to the northwest and Endako, 33 miles to the northeast. There is no settlement on or near the property. Rail transportation is accessible at the Town of Burns Lake.

## **3. Topography**

The Uncha Lake Prospect lies on the Nechako Plateau, the northernmost subdivision of the Interior Plateau (Holland, 1976). The property is located in low and rolling terrain which generally lies between 900 to 1150 metres elevation (Figures 4 and 5). The area is thickly forested with pine and bedrock is obscured by extensive drift cover. Tipper (1963) noted that over 90 per cent of the Nechako River map area is drift covered. Till and glacio-fluvial outwash are the predominant cover materials.

Outcrop is concentrated mostly on ridge crests and steep slopes. Extensive clear cut logging in the area and road building has generated additional exposures and increased access. A satellite photo of the area (Figure 6) demonstrates the active clear cutting by forestry companies. The area is known as the 'Lake District' as there are abundant small lakes created due to the subdued topography and

relatively poor drainage of the Nechako Plateau. Mineral exploration in these areas has been generally hampered by the extensive drift cover and poor exposure. The Day Claims are situated along the shallow sloped northwest face of Dayeezcha Mountain.

#### **4. Tenure**

All claims are recorded, in the name of Harold R. Oppelt, on February 11<sup>th</sup>, 2004. The property consists of 8 two-post claim units named Day #1 through Day #8 (Tenure # 408048 through 408055). A claim location map, provided in map pocket, is an adequate representation of the property outline.





Figure 2: The Nechako Plateau within the Intermontane Belt of northwestern British Columbia.

\* Uncha Lake Perlite Prospect



Figure 3: Location of Day Claims, 4.5 kms south of Uncha Lake.



MAP SHEET  
93F13E

0 km 5 km 10 km 20 km  
Scale 1: 442,645

Innovative Energy Inc.  
Uncha Lake, BC  
Day Claims  
Perlite Prospect






Figure 4: Surface elevation contours in meters of the Uncha Lake area.




Figure 5: Hillshade relief map of the Nechako River Plateau Area. Lack of shading indicates relatively low relief for area.






Figure 6: Satellite photograph of the Uncha Lake area on the Nechako Plateau. Red lines indicate access roads.




Figure 7: Photos of access into Uncha Lake perlite occurrence.

## **5. Geological Description**

### **5.1 Regional Geology**

The prospect area lies within the Nechako River NTS map sheet 93F and is entirely within the Nechako Basin of the Intermontane Belt. The Nechako River area comprises part of the Stikinia terrane. The Nechako Basin is a Mesozoic forearc basin, bounded by the Skeena Arch to the north, the Fraser River Fault System to the east, and the Yalakom Fault System and Coast Mountain plutons to the west and south. The Nechako Basin formed when Middle Jurassic terrane collisions created the Skeena Arch, which separated the Nechako Basin from the Bowser Basin to the north. Compressional and transform tectonics throughout the Cretaceous caused bordering uplands to shed clastic debris into the Nechako Basin. Strike slip faulting during the Tertiary laterally displaced surrounding terranes and numerous volcanic events mantled much of the basin with basaltic flows.

The stratigraphic succession within the study area is comprised of volcanic and sedimentary rocks of the Lower to Middle Jurassic Hazelton Group, intruded by Late Jurassic, Late Cretaceous and Tertiary felsic plutonic rocks. These are overlain by Eocene volcanics of the Ootsa Lake Group, Oligocene and Miocene volcanics of the Endako Group, and Miocene-Pliocene basalt flows.

The potential of the region to host different styles of mineral deposits has been recently recognized in the area. The Nechako Basin has the potential to host epithermal Au-Ag deposits (Uduk Lake), porphyry-related structurally hosted Au-Ag and base metals, stratabound precious metal and base metal, coal and even oil and gas seeps. The Nechako area contains 68 recorded mineral occurrences. Of these 7 are industrial mineral occurrences, 54 are base and precious metal occurrences and one coal occurrence.

## **5.2 Local Geology**

The Uncha Lake Perlite deposit occurs within the Oosta Lake Group of Eocene age. The Oosta Lake Group is comprised of mainly felsic volcanic rocks and their epiclastic derivatives.

### **5.2.1 Oosta Lake Group**

Eocene continental volcanic rocks of the Ootsa Lake Group are sporadically exposed throughout the area from the Nechako River to the west side of Francois Lake (Figure 2). Diakow and Mihalyuk (1987) recognized six lithologic divisions in the Ootsa Lake Group, which comprises a differentiated succession of andesitic to rhyolitic flows and pyroclastic rocks. Sedimentary rocks, although not common, are interspersed throughout the Oosta Lake sequence.

Potassium-argon ages of approximately 50 Ma have been obtained from Ootsa Lake rocks (Diakow and Koyanagi, 1988). Interest in the precious metal potential of the Ootsa Lake Group has increased in recent years. The Wolf and Clisbako prospects are epithermal gold-silver occurrences currently under exploration. The Wolf prospect is hosted by felsic flows, tuffs and subvolcanic porphyries, and is a low-sulphur silicified stockwork deposit (Andrew, 1988). The Clisbako prospect is hosted by Eocene basaltic to rhyolitic tuffs, flows and volcanic breccias exhibiting intense silicification and argillic alteration. Gold mineralization in both areas is associated with low-sulphide quartz stockwork zones. The Clisbako prospect has been interpreted to be a high-level volcanic-hosted epithermal system similar to those in the western United States (Dawson, 1991; Schroeter and Lane, 1992). Perlite occurrences have been described by White (1989) in deposits at Francois Lake and at Uncha Lake.







Figure 8: Generalized bedrock geology of the Uncha Lake, BC area and the Day Claims. The Uncha Lake perlite showing, on the Day Claims, occurs within rhyolite flows of the Eocene Ootsa Lake Group on the northwest flank of Dayezcha Mountain.

### **5.2.2 Uncha Lake Prospect Geology (MINFILE 93F 026)**

The Uncha Lake Perlite Showing on the Day Claims occurs within rhyolitic flows of the Oosta Lake Group on Dayeezcha Mountain. The perlite is interbedded within light to dark grey porphyritic rhyolite layers which are 2.0 to 9.0 metres thick. The perlite is light grey to pale greenish-grey with some perlitic glass occurrences. The perlite generally dips 10 to 30 degrees south and is 7.6 to 23.0 metres thick. A bedrock geology map (Figure 7) of the Uncha Lake area illustrates the extent of the Eocene age Oosta Lake Group. The Oosta Lake Group is bounded on the west by basaltic volcanics of the Late Eocene to Oligocene Endako Group.

### **5.2.3 History and Previous Work**

Originally staked in 1953 by C.S. Powney and J. Rasmussen of Fort St. James and their associates, the Uncha Lake perlite prospect has been explored by trenching and limited laboratory processing tests. British Columbia Minister of Mines reports indicate that in 1955, Technical Mines Consultants Limited exposed nineteen trenches at approximately 150 foot intervals exposing over 8000 feet of bedrock (Figure 8). Six mineable perlite layers along a zone 850 metres long and 500 metres wide were exposed. Depth of overburden increases to the northeast making further trenching impractical. The company reported that the layers are "irregular in width and attitude, lying interbedded in a folded series of rhyolites striking generally northeast and dipping about 70° to the southeast". The last trench to the southwest end of the workings exposed "three strong layers of perlite". Evidence at the time indicated that the zone extends several hundred feet farther to the southwest.

James (1955) reports the maximum exposed width of at least two layers exceeds 45 metres, and that in some places interbedded rhyolite is sufficiently narrow to permit practical open-pit mining of two or more layers from one pit. Currently the property is inactive and the old trenches are partially filled.




Figure 9: Location of perlite outcrops at Day Claims and previous trenching.

#### 5.2.4 Description of Deposit

Figure 8 shows the distribution of perlite outcrops in the prospect area and the rock types. Past company records are not available so the following description is based on field observations only.

A description of each follows:

**Perlite** is intercalated with light to dark grey porphyritic and sometimes cherty rhyolites and ranges in colour from brown to medium grey to black to pale green (Figure 10). It often has a good pearly lustre but when exposed for periods of time tends to break down into 2 to 3-centimetre subangular fragments. Uncha Lake perlite expands moderately well when heated with a hand-held propane torch often as rapidly as samples from the Frenier deposit. Glassy occurrences of perlite have a definite perlitic structure and on weathering crumbles along the perlitic cracks to a granular aggregate.





Figure 10: Photo of perlite occurrence at Trench #4.

Perlite is exposed in trenches south of the access road but not enough bedrock is exposed to determine whether these occurrences represent a single unit. Overburden varies from a few inches to several feet through the property (Figure 11). Significantly, fresh, medium grey perlite is exposed along a ridge west of the trenched area. Structural information is limited but exposures in trenches indicate the host rhyolite strikes northeast and dips steeply southwest.





Figure 11: Photo of Perlite occurrence at Trench #2.

**Rhyolite**, in sharp contact with perlite, ranges from white to dark grey in colour. The rhyolite is a very hard, very fine grain volcanic flow unit which can form ledges and small outcrops up to 25 feet in diameter (Figure 12). Both white and grey varieties contain 1 to 7-centimetre bands of darker "cherty" quartz (chalcedony?) or patches, up to 3 centimetres across, of light green silica possibly indicative of hydrothermal alteration. Rhyolite is occasionally porphyritic with 1 to 5-centimetre rectangular phenocrysts of potassium feldspar in a fine-grained matrix. Flow banding is evident in some occurrences of the white rhyolites. Near the southern end of the access road siliceous angular fragments, 5 to 7 centimetres across, are observed in rhyolite. A black, very hard, porphyritic rhyolite with rectangular phenocrysts of potassium feldspar occurs at the south-east portion of Trench #6 near the edge of the cleared area.



Figure 12: Photo of white rhyolite. Note flow banding steeply dipping southeast; occurrence along access road between Trench #4 and #5.



## 6. Uncha Lake Perlite Physical Properties

### 6.1 Physical Properties

In 1989, CANMET conducted testing of rock samples from various known perlite properties in British Columbia to assess the potential for perlite resources. The samples were subjected to three tests. Tests included the determination of water loss when heated to 800° C (Figure 13); the second determined the softening temperature of the samples (Figure 14); and the third was a measurement of the change in bulk density due to expansion (Figure 15). All perlite occurrences were successfully tested for expansion. The graphs below provide a comparison of the samples tested. It should be noted that the Uncha Lake perlite samples compare favourably to the Frenier deposit and Francois Lake, the only expanding perlite deposits that have been previously mined in BC.

### Perlite Content of Various British Columbia Deposits




Figure 13: Histogram showing perlite content of samples from Gold Creek, Uncha Lake, Frenier, Francois Lake, Blackwater Creek and Florence Creek.

*Taken from EMPR Geological Fieldwork 1990, Paper 1991-1.*




Figure 14: Softening temperatures of perlite samples from Gold Creek, Uncha Lake, Oosta Lake, Frenier, Francois Lake, Blackwater Creek and Florence Creek.  
 Taken from EMPR Geological Fieldwork 1990, Paper 1991-1.




Figure 15: Bar chart indicates the change in bulk density observed due to expansion of perlite samples from Frenier, Oosta Lake, Blackwater Creek and Florence Creek. Uncha Lake sample is comparable to the Frenier and Oosta Lake deposits.  
 Taken from EMPR Geological Fieldwork 1990, Paper 1991-1.




## **7. Conclusions and Recommendations**

Previous exploration efforts on the Uncha Lake property indicate the presence of perlite within rhyolite flows of the Eocene-aged Oosta Lake Group. Systematic trenching had been undertaken on the property tracing perlite exposures for approximately 850 metres along the northwest slope of Dayeezcha Mountain. The perlite layers are between 7.5 metres and 23 metres thick and appear to be intercalated with porphyritic rhyolite flows and tuffs. The perlite rock exhibits definite perlitic structure and on weathering crumbles along the perlitic cracks to a granular aggregate. Testing by CANMET indicates the Uncha Lake Perlite has a moderate well expansion rating, water loss content of 3.2% and a softening temperature range of 1240 to 1260°C.

Additional geologic mapping is required to complete the historical property scale mapping. This would also yield a better understanding of structural geology and stratigraphy. Systematic trenching is recommended to expose the perlite due to the overburden layer. Assuming favourable results are obtained from preliminary work, diamond drilling of perlite occurrences would aid in assessing reserve potential and continuity of perlite layers. The excellent access provided by logging activity in the area would allow for significant cost savings related to mobilization and road construction.

## **Appendix 1**

### **Claim Location Map and Tenure Details**



**Uncha Lake Project**

<b>Project</b>	<b>Ownership</b>	<b>Claim Name</b>	<b>Tenure Number</b>	<b>Map Number</b>	<b>Expiry Date</b>	<b>Mining Division</b>	<b>Tag Number</b>
Uncha Lake	HR Oppelt	Day 1	408048	93F13E	Feb 11, 2005	Omineca	721791
Uncha Lake	HR Oppelt	Day 2	408049	93F13E	Feb 11, 2005	Omineca	721792
Uncha Lake	HR Oppelt	Day 3	408050	93F13E	Feb 11, 2005	Omineca	721793
Uncha Lake	HR Oppelt	Day 4	408051	93F13E	Feb 11, 2005	Omineca	721794
Uncha Lake	HR Oppelt	Day 5	408052	93F13E	Feb 11, 2005	Omineca	721795
Uncha Lake	HR Oppelt	Day 6	408053	93F13E	Feb 11, 2005	Omineca	721796
Uncha Lake	HR Oppelt	Day 7	408054	93F13E	Feb 11, 2005	Omineca	721797
Uncha Lake	HR Oppelt	Day 8	408055	93F13E	Feb 11, 2005	Omineca	721798




**Appendix 2**

**Geological Mapping**




**And**

**Sample Descriptions**

**May 2004**



Legend


-  29 Sample Point (See Outcrop Descriptions)
-  Road cut
-  Edge of Logged Trees

**Innovative Energy Inc.**

**Uncha Lake Perlite Occurrence**

Location of Trenches  
and Sample Points

May/2004



### Legend


- P** – Perlite Occurrence
- V** – White Rhyolite
- O** – Obsidian with Phenocrysts

**Innovative Energy Inc.**

**Uncha Lake Perlite Occurrence  
Outcrop Distribution**

May/2004





### Legend


-  - Perlite Occurrence
-  - White Rhyolite
-  - Black Obsidian with Phenocrysts

**Innovative Energy Inc.**

Uncha Lake Perlite Occurrence  
Distribution of Perlite

May/2004





N53°57'

N53°55'48"

Uncha Lake

N53°54'36"

N53°53'24"

N53°52'12"

53 51 15 N 125 38 10 W

53' W125°49' W125°45' W125°41' NW125°37' W125°33' W125°29' W125°25'

N53°49'48"

N53°48'36"

N53°47'24"

N53°45'

Image © 2005 DigitalGlobe  
Image © 2005 MDA EarthSat  
© 2005 TeleAtlas

© 2005 Google

Pointer 53°51'00.72" N 125°37'44.79" W elev 3374 ft Streaming ||||| 100% Eye alt 18.73 mi



Uncha Lake

53 51 15 N 125 38 10W



Image © 2005 DigitalGlobe  
Image © 2005 MDA EarthSat

©2005 Google

Pointer 53°51'22.99" N 125°38'09.32" W elev 3703 ft Streaming [progress bar] 100% Eye alt 12.31 mi



53 51 15 N 125 38 10W

Image © 2005 DigitalGlobe  
© 2005 TeleAtlas

© 2005 Google

Pointer 53°51'14.94" N 125°38'13.73" W elev 3682 ft Streaming ||||| 100% Eye alt 15898 ft



**Uncha Lake  
Perlite<sup>1</sup>**

(55° 125' N.W.) In July, 1953, forty-two claims were located on Davyezcha Mountain, about 25 miles south of Burns Lake, to cover a new discovery of perlite. The claims, comprising the Raudy Nos. 1 to 8, Jimmy Nos. 1 to 8, National Nos. 1 to 6, Shiela Nos. 1 to 7, Shallamar Nos. 1 to 8, Stewart Nos. 1 to 3, and Willow Nos. 1 and 2, were recorded by C. S. Powney and John Rasmussen, of Fort St. James; William H. Anderson, of Prince George; and others. The main showings are on the north and west slopes on the mountain at elevations of 3,200 to 3,700 feet. They are reached from Southbank on Francois Lake by 12 miles of road to the south side of Uncha Lake, thence about 3½ miles across country southward to a tent camp established at an elevation of about 3,000 feet. The northwest side of the mountain has a gentle slope, is lightly timbered, and outcrops of bedrock are not plentiful.

Perlite appears to be intercalated with light- to dark-grey porphyritic rhyolites which are probably comparable to the Eocene or Oligocene rhyolitic flows and tuffs mapped<sup>2</sup> by Armstrong on the north side of Francois Lake. In no instance were the rocks directly overlying or underlying the perlite seen.

Three separate occurrences of perlite were visited. The highest one is at an elevation of approximately 3,700 feet. There a shallow trench exposes 6 feet of pale-greenish-coloured perlite beside 4 feet of resinous brown perlitic glass. A small exposure 75 feet away shows 6 to 8 feet consisting of alternating bands of stony porphyritic rhyolite and 4- to 12-inch layers of resinous brown perlitic glass. The flow lines strike north 70 degrees northwest.

Downhill from this exposure the rocks are dark-grey to black porphyritic rhyolite, in which the flow layers strike north 40 degrees east and dip 65 degrees northwest.

Farther to the southwest and at an elevation of about 3,550 feet, a line of holes 1 to 3 feet deep dug through the overburden indicates that perlite extends across a width of possibly 150 feet. No natural exposures of perlite are to be seen at this place.

<sup>1</sup> By R. R. King  
<sup>2</sup> By J. W. Armstrong  
<sup>3</sup> By Stuart S. Holland  
B. Geol. Surv., Canada, Mem. 102, p. 73, and Map 9012.

OUR REPORT COVERS UP TO 3200 FEET THIS INFORMATION  
REPORTS A FURTHER DEPOSIT UP TO 3700 LEVEL  
AN ADDITIONAL 500 FEET WITH VARIOUS OUTCROPS  
I CONSIDER THIS A VERY INTERESTING DISCOVERY FROM  
THE ARCHIVE FILES IN VICTORIA

About 2,000 feet farther southwest and at an elevation of about 3,250 feet, perlite outcrops in a bluff 20 feet across and 10 feet high. Other outcrops and pits indicate that the perlite extends across a maximum width of about 100 feet and has a length of at least 250 feet. Flow layers in this area strike northeast and dip 40 degrees southeast.

The perlite in the several showings is light grey or pale-greenish grey in colour. The glass has a definite perlitic structure and on weathering crumbles along the perlitic cracks to a granular aggregate. The glass has a few feldspar phenocrysts and displays imperfectly developed flow lines. In this section numerous tiny crystallites are seen to be arranged in parallel orientation.

Laboratory tests on the brown resinous glass and the greenish-grey perlite indicate that both expand moderately well.

THIS PROPERTY  
UNCHA LAKE  
IS ENLARGED  
CONTAINS 21 CLAIMS NOT 8.









































# BCGS Geology

## Mineral Inventory Layers


-   **MINFILE status**  
✕ Developed Prospect  
✕ Past Producer  
✕ Producer  
▲ Prospect  
▲ Showing  
■ All Others

-   **MINFILE number label**  
✕ Developed Prospect  
✕ Past Producer  
✕ Producer  
■ Prospect  
■ Showing  
■ All Others

## Mineral Titles Layers

-   **MTO Mineral Titles Online solid**  
■ Mineral  
■ Placer

## Topographic Layers



SCALE 1 : 103,063



002

H OPPELT

13:02

06/22/04

**WORLDWIDE LABORATORIES**  
**ANALYTICAL SERVICES**  
**100 MILL TONNES OR ROCK WOOL INS**


100 Mill  
 Tonnes  
 or Rock  
 Wool Ins

Perlite

SAMPLES	SiO2	Al2O3	Fe2O3	MgO	CaO	Na2O	K2O	TiO2	P2O5	MnO	Cr2O3	Ba	Ni	Sr	Zr	Y	Nb	Sc	LOI	Y2O3	ZrO2	SUM
	%	%	%	%	%	%	%	%	%	%	%	ppm	ppm	ppm	ppm	ppm	ppm	ppm	%	%	%	%
TERRACE MTH	66.68	17.28	3.80	1.38	4.64	4.37	3.15	.80	.26	.06	.002	1766	20	1884	297	17	71	6	3.4	.02	.02	100.22
TERRACE MTH #1	61.38	15.14	2.09	.48	3.16	1.69	5.00	.39	<.01	.03	<.001	863	<20	369	368	21	124	4	10.2	.05	.01	99.76
TERRACE MTH #2	41.96	9.68	1.20	.53	12.54	1.15	3.76	.26	.01	.02	<.005	535	<20	801	229	14	84	1	12.8	.18	7.12	84.09
TERRACE MTH #3	65.79	14.80	2.03	.37	1.66	3.75	5.17	.43	.03	.06	<.001	865	<20	319	373	25	135	3	5.7	.00	.08	99.99
TERRACE MTH #4	63.77	14.38	1.51	.70	2.79	1.16	4.60	.39	<.01	.03	<.001	706	<20	380	377	27	157	3	10.2	.04	.03	99.72
TERRACE MTH #5	65.75	15.01	2.08	.35	1.73	3.83	4.12	.42	.03	.06	<.001	811	<20	326	368	26	125	4	6.4	.02	.01	99.99
TERRACE MTH #7	61.97	14.71	1.88	.85	2.92	1.36	4.59	.42	.02	.07	<.001	842	<20	382	379	23	162	4	10.7	.06	.01	99.63
TERRACE MTH #8	63.12	14.41	1.86	.93	3.06	1.49	3.77	.41	.04	.05	<.001	839	<20	367	354	22	130	4	10.5	.03	.01	99.98
TERRACE MTH #9	64.54	13.79	1.65	.30	1.44	3.13	5.22	.39	<.01	.04	<.001	719	<20	281	348	22	141	3	8.9	.02	.01	99.98
TERRACE MTH #10	65.71	14.67	2.08	.41	1.42	3.71	4.92	.44	.04	.06	<.001	703	<20	277	373	29	168	5	6.3	.01	.01	98.95
TERRACE MTH #11	62.37	15.09	1.81	.75	2.86	1.39	4.73	.41	.01	.03	<.001	837	<20	343	336	27	123	3	10.3	.04	.01	99.94
TERRACE MTH #13	52.36	13.54	8.50	7.97	7.22	2.08	2.70	.98	.47	.14	.074	1056	245	736	130	22	410	23	3.9	.07	.00	100.19
TERRACE MTH #14	59.32	17.97	3.37	1.63	4.51	3.34	4.90	.82	.27	.05	.004	1845	<20	1228	300	18	71	4	3.4	.02	.03	99.99
TERRACE MTH #17	66.42	14.88	1.99	.63	1.66	4.89	4.50	.43	.05	.07	.003	790	<20	389	364	27	149	4	5.0	.02	.00	99.71
TERRACE MTH #18	62.85	15.36	3.23	.69	2.58	1.66	3.11	.66	.54	.02	.006	1747	33	1077	209	11	48	7	8.9	.46	1.16	99.96
RE TERRACE MTH #18	62.77	15.39	3.24	.69	2.60	1.68	2.96	.65	.53	.02	.005	1753	<20	1078	190	<10	14	8	9.1	.45	1.14	100.08
UNCHA TR #3	73.78	12.14	1.17	.08	.36	3.15	5.22	.17	<.01	.07	<.001	63	<20	21	190	55	58	2	3.8	.03	.01	99.99
UNCHA TR #3A	73.85	12.15	1.18	.13	.47	3.06	5.36	.17	<.01	.07	<.001	128	<20	51	183	54	60	2	4.3	.02	.01	100.08
UNCHA TR #4	74.02	12.12	1.10	.08	.37	3.28	4.88	.17	<.01	.07	<.001	177	<20	47	184	51	53	1	3.9	.02	.01	100.05
UNCHA TR #5	74.08	12.13	1.08	.05	.29	2.86	5.51	.17	<.01	.06	<.001	25	<20	<10	187	60	52	2	3.7	.03	.01	99.98
UNCHA TR #6	72.94	12.64	1.19	.14	.51	3.23	5.82	.20	<.01	.07	<.001	6	<20	34	256	70	51	3	4.0	.01	.01	100.00
UNCHA TR #6A	73.53	12.76	1.11	.06	.29	3.39	5.18	.17	<.01	.07	<.001	6	<20	<10	196	55	60	2	6.8	.01	.01	99.99
6 MILE BOLEAN	61.20	13.73	8.33	3.88	13.64	3.17	3.28	.56	.37	.16	.002	1155	27	675	58	13	110	21	11.2	2.29	1.60	99.65
STANDARD SD-17/CS8	61.66	13.85	5.78	2.36	4.69	4.17	3.41	.68	1.00	.53	.462	401	35	311	351	24	26	24	3.4	2.40	5.31	99.95

GROUP 1A - 0.200 CM SAMPLE BY LIBOS FUSION, ANALYSIS BY ICP-ES. LOI BY LOSS ON IGNITION.  
 TOTAL C & S BY LECD. (NOT INCLUDED IN THE SUM)  
 - SAMPLE TYPE: ROCK PULP  
 Samples beginning 'RE' are Return and 'RRE' are Reject Return.

Date: 1/7A DATE RECEIVED: JUN 15 2004 DATE REPORT MAILED: Jun 22/04



(All results are considered the confidential property of the client. Acme assumes the liabilities for actual cost of the analysis only.)

001



SAMPLE#	SiO2	Al2O3	Fe2O3	MgO	CaO	Mn2O	K2O	TiO2	P2O5	Na2O	Cr2O3	Ba	Ni	Br	Zr	Y	Nb	Sc	LOI	TOT/C	TU/TS	MM
	%	%	%	%	%	%	%	%	%	%	%	ppm	ppm	ppm	ppm	ppm	ppm	ppm	%	%	%	%
SILICED PERLITE	72.92	13.08	.70	.06	.72	4.05	4.50	.05	<.01	.10	<.001	73	<20	27	64	30	92	4	3.8	.02	.01	100.03
ORG PERLITE	73.79	12.72	.74	.04	.52	3.42	4.92	.05	<.01	.70	<.001	13	<20	<10	77	27	66	4	3.7	.02	.01	100.02
SUPREME PERLITE BRECKON US	73.83	13.30	.83	.06	.84	3.70	4.18	.03	<.01	.86	<.001	268	<20	51	61	21	<10	2	3.9	.01	<.01	100.01
GRADE 1240 317.56	73.79	13.18	.66	.05	.57	4.27	4.36	.07	<.01	.09	<.001	13	<20	<10	90	26	66	3	2.7	<.01	.01	99.96
GRADE 4500 270.46	72.81	13.81	.75	.05	.56	4.17	4.75	.07	<.01	.09	<.001	8	<20	<10	101	27	82	3	3.7	.02	.01	99.99
STANDARD 90-17/CBB	61.66	13.85	5.70	2.36	4.69	4.17	1.42	.60	1.00	.53	.442	401	33	311	351	24	26	23	3.4	2.39	5.32	99.96


GROUP 4A - 9.200 GM SAMPLE BY L1802 FUSION, ANALYSIS BY ICP-ES. LOI BY LOSS ON IGNITION.  
 TOTAL C H S BY LECD. (NOT INCLUDED IN THE SUM)  
 - SAMPLE TYPE: SAND PULP

Lab # FA DATE RECEIVED: JUN 15 2006 DATE REPORT MAILED: June 21, 04



SAMPLES  
 OF IMPORT Rock  
 ANALYSED FOR  
 COMPARISON TO  
 UNCHA LAKE Rock





No virus found in this incoming message.

Checked by AVG Free Edition.

Version: 7.1.361 / Virus Database: 267.12.5/149 - Release Date: 10/25/2005

**UNCHA LAKE PERLITE DEPOSIT OUTCROP / TRENCH DESCRIPTIONS**

<b>Trench #</b>	<b>Map Point</b>	<b>Elev</b>	<b>UTM Easting</b>	<b>UTM Northing</b>	<b>Sample #</b>	<b>Photo #</b>	<b>Description</b>
1	3	955	325745	5971517	-	-	Trench all deep cover; no exposures
2	4	962	325621	5971396	-	13	<b>Start</b> of Trench #2
2	36	956	325623	5971388	2.3	46,47	<b>Perlite</b> ; Dark green, very friable, pearly luster, v. large crystal face; dug small trench.
2	5	974	325637	5971372	-	-	<b>Rhyolite</b> ; 2' wide outcrop very hard white rhyolite
2	6	955	325666	5971341	-	-	<b>Rhyolite</b> ; End of white rhyolite from above outcrop
2	7	966	325681	5971361	2.1	19	<b>Perlite</b> ; dk grey to brown, pearly luster; v. friable to white powder; dug small 2' pit goes up for ~20 feet up trench then lose it due to cover.
2	8	1038	325709	5971292	-	-	Possible float?; ultra hard v.f.g. rhyolite; dark olive color; cherty; conchoidal fracture
2	9	1007	325693	5971292	2.2	20,21	<b>Perlite</b> ; Near end of trench; dk green rhyolite; semi-pearly luster; v. friable turns to powder as sample 2.1; dug two holes along trench same material for 30 ft or more.

Trench #	Map Point	Elev	UTM Easting	UTM Northing	Sample #	Photo #	Description
3	10	972	325498	5971301		14, 15	Start of Trench #3
3	11	975	325505	5971289	3.1	24	<b>Perlite</b> ; pearly luster; dk green large crystal faces; v. friable turns to white powder; dug small pit to see exposure
3	12	989	325520	5971271		25	No outcrop; only float; Gerry took sample here; dug small holes no rock in place
3	13	993	325532	5971258	3.2	26,27	<b>Perlite</b> ; dk to med green large crystal faces; v. friable turns to white powder; looks slightly cherty; grades laterally down slope into more friable dk green large crystal material as in sample 3.1; dug trench for 15 – 20 ft in same material; Photo 27 is photo of trench of same material; appears bed continues for >40 ft; upslope of trench is an outcrop of v. hard rhyolite (Map Point 14).
3	14	995	325541	5971245	-	28	<b>Rhyolite</b> ; outcrop, very hard, dark grey, v.f.g.; outcrop 10 ft in diameter; ledge forming
3	15	991	325551	5971236	3.3	-	<b>Rhyolite</b> ; v.f.g. siliceous cherty; light grey in color, very hard; conchoidal fracture; outcrop 3 ft in diameter
3	16	992	325562	5971215	-	-	<b>Rhyolite</b> ; siliceous appearance, v hard; outcrop 10 ft in diameter; same material as Map Point #14
3	17	997	325580	5971204	-	-	<b>Rhyolite</b> ; same as above; outcrop is 20 ft in diameter
3	18	996	325594	5971195	-	29	<b>Rhyolite</b> ; same as above; outcrop is 7 ft in diameter; marks <b>END</b> of Trench
3	19	999	325610	5971186			Upper road 15m south of end of Trench 3



Trench #	Map Point	Elev	UTM Easting	UTM Northing	Sample #	Photo #	Description
4	20	979	325432	5971265	-	16,17, 30	<b>Start</b> of Trench #4 @ Road bed
4	21	985	325434	5971248	4.1	31	<b>Perlite</b> ; dk. green large crystal face, very friable as in trench #3; dug hole to find exposure; sample point is about 30 ft from start of trench; perlite bed may occur for more than 60 ft along trench.
4	22	992	325452	5971218		32	<b>Rhyolite</b> ; very hard, not friable; outcrop; same material as Map Point 18
4	23	999	325479	5971191		33	<b>Rhyolite</b> ; very hard material same as above.
4	24	1005	325508	5971146	4.2	34,35,36,37	<b>Perlite</b> ; semi-pearly luster, large crystal faces, dark green; turns to white powder; not as friable as other trench samples; moderately hard to break; test individual pieces for any change in expansion; material seems to present until end of trench; weathers to a med brown sand; sand is abundantly present for 90 ft; possible extension of this material is the sand piles; 3 photos (35-37) of sandy material.
4	25	1013	325522	5971118	-	-	<b>End</b> of Trench #4; same material as above
Lower Roadcut	26	985	325369	5971209	-	-	<b>Rhyolite</b> ; on access road towards Trench #5; v. hard rhyolite, v.f.g., not friable; outcrop is 5 ft in diameter; lots of float around
Lower Roadcut	27	993	325331	5971183	-	38	<b>Rhyolite</b> ; on access road towards Trench #5; v.f.g.; flow banding in rhyolite

<b>Trench #</b>	<b>Map Point</b>	<b>Elev</b>	<b>UTM Easting</b>	<b>UTM Northing</b>	<b>Sample #</b>	<b>Photo #</b>	<b>Description</b>
5	28	993	325318	5971175	5.1	39,40	<b>Start of Trench;</b> Rhyolitic; conglomeratic looking, coarse crystalline; purple colored; outcrop 5' in diameter; Photo 40 of roadbed looking northeast.
5	29	1001	325321	5971125	-	41	<b>Rhyolite;</b> off trench area; large outcrop >25 ft in diameter of v. hard, light grey to purple color, v.f.g.; flowbanding dips 70° SE
5	30	1002	325357	5971122	-	-	<b>Rhyolite;</b> as above; 15 ft diameter outcrop
5	31	1008	325385	5971078	-	42	Pit; open pit filled with water; Must have taken bulk sample from this pit. 50m east of here is a small trench dug by backhoe for sampling in perlite; Possible perlite occurrence towards end of Trench #5.
5	32	1007	325417	5971046	-	-	<b>End of Trench.</b>

<b>Trench #</b>	<b>Map Point</b>	<b>Elev</b>	<b>UTM Easting</b>	<b>UTM Northing</b>	<b>Sample #</b>	<b>Photo #</b>	<b>Description</b>
6	35	1005	325228	5971069	-	-	<b>Start</b> of Trench #6, very swampy.
6	34	1009	325327	5970974	6.1	44, 45	<b>Obsidian;</b> black with large phenocrysts of feldspar, large crystal faces; off trench area; large outcrop >25 ft in diameter of v. hard.
6	33	1007	325349	5970951	-	43	<b>End</b> of Trench



LABORATORY TESTING OF PERLITE SAMPLES

1. Conditions - 1 lb gas pressure with 24 litres air/min at 800°C.

	<u>Expansion</u>	<u>Expansion Ratio</u>	<u>% Expansion</u>
Standard (Uros, new Oct 75)	330	1 : 32	
Canadian Sample No. 1	180	1 : 18	56.25
Canadian Sample No. 2	200	1 : 20	62.50
Canadian Sample No. 3	50	1 : 6	18.75
Canadian Sample No. 4	50	1 : 5	13.62
Canadian Sample No. 5	20	1 : 2.4	7.5
Standard (Uros, new 76)	330	1 : 33	
Milos	175	1 : 17.5	

2. Conditions - 2 lb gas pressure with 24 litres air/min at 700°C.

Standard (Uros, new Oct 76)	370	1 : 37	
Canadian Sample No. 1	160	1 : 14	41.97
Canadian Sample No. 2	220	1 : 22	59.47
Canadian Sample No. 3	140	1 : 14	38.29
Canadian Sample No. 4	190	1 : 19	48.71
Canadian Sample No. 5	20	1 : 2	5.12
Standard (Uros new Oct 76)	370	1 : 37	
Milos	285	1 : 28.5	

\* Percentages sample against Uros Standard

7. Worst case 3.2% expansion


	<u>Expansion</u>	<u>Expansion Ratio</u>	<u>% Expansion</u>
3. Conditions - 6 lb gas pressure with 32 litres air/min at 1000°C.			
Standard (Uras, new Oct 76)	330	1 : 33	
Canadian Sample No. 1	180	1 : 18	54.54
Canadian Sample No. 2	260	1 : 26	78.78
Canadian Sample No. 3	120	1 : 12	36.36
Canadian Sample No. 4	200	1 : 20	60.60
Canadian Sample No. 5	28	1 : 2.8	8.48
Standard (Uras, new Oct 76)	330 (Fusing flame)		
Allies	260 (Slight fusion)	1 : 28	

† Due to the fusion of the standard at 1000°C it was thought inadvisable to attempt to expand a sample at 1100°C as this would cause delays due to the switching off of the expander in order to clear the expansion chamber of fused material.

4. Conditions - 12 lb gas pressure with 36 litres air/min at 1100°C.

Canadian Sample No. 1	180	1 : 18	
Canadian Sample No. 2	260	1 : 26	
Canadian Sample No. 3	140	1 : 14	
Canadian Sample No. 4	All material used up		
Canadian Sample No. 5	28	1 : 2.8	
There were signs of the Canadian Perlite beginning to fuse in the expansion chamber at this temperature.			
Allies	200	1 : 20	Fusing readily

\* Percentage sample against Uras Standard



**KEY**

- O— Canada 1
- A— Canada 2
- D— Canada 3
- B— Canada 4
- X— Canada 5
- M— Milco
- Z— Uros standard

UNCHA LAKE — BRITISH COLUMBIA

Fig. No. 1

PERLITE EXPANSION RATIOS

## Programs & Services

Ministry of  
Energy & Mines

Ministry News Ministry Search Reports & Publications Site Map Contacts

## MINFILE Capsule Geology and Bibliography

[MINFILE Home page](#)

[Main Search Menu](#)

[Back to Search Results](#)

[ARIS Home page](#)

### Capsule Geology and Bibliography

093F 026

<b>Name</b>	UNCHA LAKE	<b>Mining Division</b>	Omineca
<b>Status</b>	Showing	<b>NTS</b>	093F13E NAD 27
<b>Latitude Longitude</b>	53 51 15 N 125 38 10 W	<b>UTM</b>	10 5970301 326613
<b>Commodities</b>	Perlite	<b>Deposit Types</b>	R12 : Volcanic glass - perlite.
<b>Tectonic Belt</b>	Intermontane	<b>Terranes</b>	Stikine.

#### Capsule Geology

The region in which the Uncha Lake showing occurs is within the Intermontane Belt, underlain dominantly by Lower to Middle Jurassic volcanic and sedimentary rocks of the Hazelton Group. These assemblages are overlain by the Upper Cretaceous to Lower Tertiary Ootsa Lake Group and Miocene plateau basalt. Intruding Lower Jurassic rocks of the Hazelton Group in the northeastern part of the map sheet is a belt of granodiorite, diorite and quartz diorite plutons of the Lower Jurassic Topley intrusive suite. Felsic plutons of probable Cretaceous age intrude both Lower and Middle Jurassic Hazelton strata.

The Ootsa Lake Group of Upper Cretaceous to Lower Tertiary age comprises mainly felsic volcanic rocks and their epiclastic derivatives. The Uncha Lake perlite showing occurs within rhyolite of this group on Dayeezcha Mountain. The perlite dips 10 to 30 degrees south and is 7.6 to 23.0 metres thick. The perlite is interbedded within light to dark grey porphyritic rhyolite layers 2.0 to 9.0 metres thick. The perlite is light grey to pale greenish-grey,



some perlitic glass occurrences in the area are resinous brown.

**Bibliography**

EMPR AR \*1953-194; 1955-97  
EMPR EXPL 1976-E206; 1977-E253; 1978-E289, 1992-69-106  
EMPR FIELDWORK 1992, pp. 475-481; 1993, pp. 9-14, 39-44; 199  
pp. 167-170, 193-197  
EMPR OF 1994-19  
EMPR PF (Monthly Report, Smithers Office, Feb. 1979; Report on  
Uncha Lake Perlite, 1977)  
GSC MAP 1131A; 1424A  
GSC MEM 324, p. 54  
GSC P 90-1F, pp. 115-120  
GCNL #231, 1979

*Database last posted: February 05, 2003*

Go to: [Main Search Menu](#); [MINFILE Name/No. Search](#); [Commodity/Status/NTS Search](#); [Deposit Type Search](#); [Tectonic Belt/Terrane/Latitude/Longitude Search](#)

[MINFILE Home page](#)

This page last updated: June 11, 2001

This report covers up to 3200 feet elevation. The above information indicates a Further deposit extends up to the 3700 foot level, Upon further inspection via Second field trip we have verified the above information for a further 500 feet Showing several large outcrops on the north and west side of Dayeezcha Mountain., As a result of this field trip the deposit is enlarged to 21 cells from The original 8 cells.

Harold R. Oppert.

## APPENDIX D


### STATEMENT OF QUALIFICATIONS

1. Harold Richard Oppelt Of 21664 Monahan Court, Langley B>C, do hereby declare the following.

1. I have worked as a prospector in Mineral Exploration for the past 38 years,
2. I have worked on several prospects and developed prospects in Alberta and in British Columbia during the years 1967 to 2006.
- 3 I am responsible for the preparation of this report and I am the sole owner of the Day Claims.
4. I visited the claims group on June 18 to 22 2004,

Signed Harold Richard Oppelt





# M093F082

## MINERAL LEGEND

- ADMINISTRATIVE AREAS**
- MINING DIVISION(S):  
NUMBER
- LAND DISTRICT(S):  
RANGE 4 COAST
- REGIONAL DISTRICT(S):  
BULKLEY-NECHAKO
- ADMINISTRATIVE BOUNDARIES**
- REGIONAL DISTRICT  
MINING DIVISION  
LAND DISTRICT  
PROVINCIAL BOUNDARY  
MUNICIPALITY
- NO STAKING AREA**
- PARK**
- INDIAN RESERVE**  
(SEE NOTES 1)
- CONDITIONAL AREA**  
SUBJECT TO CONDITION RESERVE.  
RELEASE REQUIRED RESERVE.  
OR URANIUM / THORIUM REGULATION  
(SEE NOTES 3)

- MINERAL TENURES**
- MINERAL CLAIM
- MINING LEASE
- INDUSTRIAL MINERAL TITLE
- MINING LEASE
- INDUSTRIAL MINERAL CLAIM NAME
- TENURE NUMBER
- TAG NUMBER
- CLAIM SIZE (UNITS)
- LEGAL POST
- WITNESS POST
- TENURE HOOK
- VERIFIED
- SURVEYED
- GLOBAL POSITIONING SYSTEM
- CROWN GRANTED 2 POST CLAIM
- F LOT (Real Estate Lot)
- REVERTED C.G. 2 POST CLAIMS**
- Reverted C.G. (Not Open for Staking)
- BID LOT
- R.C.G. (Issued under a former Act)

- PLANIMETRIC LEGEND**
- DRAINAGE AND RELATED FEATURES**
- COASTLINE, DEFINITE  
INDEFINITE
- RIVER / STREAM, DEFINITE  
INDEFINITE
- LAKE, DEFINITE  
LAKE, INDEFINITE
- DAM
- DYKE
- SAND / GRAVEL BAR
- FLOODED LAND
- SWAMP / MARSH
- FALLS / RAPIDS
- ICE FIELD / GLACIER
- RESERVOIR, DEFINITE  
RESERVOIR, INDEFINITE
- CLIFF / SCARP
- ESKER
- SLIDE
- LANDMARK FEATURE**
- MINE
- PIER / WHARF
- PIPELINE
- QUARRY
- TRANSMISSION LINE
- TRANSPORTATION FEATURES**
- AIRFIELD
- OUTLINE / SEISMIC LINE
- RAIL LINE
- ROAD, SURFACE PAVED
- ROAD, SURFACE LOOSE
- ROAD, SURFACE ROUGH / TRAIL
- BRIDGE
- CONTROL DATA**
- HORIZONTAL CONTROL POINT, MARKED
- VERTICAL CONTROL POINT, MARKED
- MAJOR CONTOUR
- MINOR CONTOUR
- CONTOUR INTERVAL - 20 METRES

### DISCLAIMER

This map is prepared only as a guide to the location of mineral tenures as shown on the locator's sketches. For current or more specific information, application should be made to the appropriate Gold Commissioner.

**SOURCES OF INFORMATION**

Planimetric and topographic information obtained from the Terrain Resource Information Management (TRIM) base mapping program. For more information contact: Base Mapping and Geomatics Services Branch Ministry of Sustainable Resource Management.

Source Date: 2002 OCT 28

Cadastral produced from spatial data obtained from the Crown Land Registry Services (CLRS). For more information contact the Crown Land Registry Services, Ministry of Sustainable Resource Management.

Source Date: 2002 AUG 06

This map depicts only the mineral tenure theme. For the placer tenures theme see appropriate placer map and for the coal tenure theme see appropriate coal map.

Additional tenure information is available on the Internet:  
<http://srmwww.gov.bc.ca/mida>

### NOTES FROM MINERAL LEGEND

1. For Uranium and Thorium Regulations, please refer to Mines Act.

**MISCELLANEOUS NOTES**

Staking is not permitted over all Crown Granted Lots issued since August 15, 1985. (B.C. Reg. 138 / 94)

Staking is not permitted within tidal waters. (B.C. Reg. 100 / 88)


Surface lots with mineral rights are not shown.

Please refer to the Mineral Tenures Act, Mineral Tenure Act Regulation, Mines Act, and the Guide to Staking in British Columbia for more complete information.


### GOLD COMMISSIONER OFFICES

- CARIBOO**  
102 350 Balfour Ave.  
Queens BC V2J 2C1  
Public Query: (250) 992-4313  
FAX: (250) 992-4314  
Mining Division: Cariboo
- VANCOUVER ISLAND**  
8th floor, 1810 Blanshard Street  
P.O. Box 9322 Stn Prov Govt  
Victoria BC V8W 9R3  
Public Query: (250) 952-0567  
FAX: (250) 952-0541  
Mining Divisions: Albert, Nanaimo, and Victoria
- OMINECA**  
1020 Murray Street, Bag 5000  
Smithers BC V1J 2N6  
Public Query: (250) 847-7207  
FAX: (250) 847-7232  
Mining Division: Omineca
- COAST / LIARD**  
302 865 Hornby Street  
Vancouver BC V5Z 2C5  
Public Query: (604) 660-2872  
FAX: (604) 660-2653  
Mining Divisions: Adm. Clinton, Liard, Liocot, Skeena, New Westminster, and Vancouver
- KAMLOOPS / OKANAGAN**  
250 455 Columbia Street  
Kamloops BC V2C 6K4  
Public Query: (250) 828-4544  
FAX: (250) 828-4233  
Mining Divisions: Kamloops, Nicola, Osoyoos, Revelstoke, Simikamean, and Vernon
- EAST KOOTENAY**  
100 Cantara Street North  
Cranbrook BC V1C 3P8  
Public Query: (250) 426-1241  
FAX: (250) 426-1254  
Mining Divisions: Fort Steele and Golden
- KOOTENAY**  
310 Ward Street  
Nelson BC V1L 5S4  
Public Query: (250) 354-6103  
FAX: (250) 354-6407  
Mining Divisions: Greenwood, Nelson, Shuswap, and Trail Creek

### GUIDE TO BCGS MAPPING SYSTEMS



### GUIDE TO THE MINERAL TITLES ONLINE GRID SYSTEM



MAGNETIC DECLINATION AS OF 2004

CHANGING 12.2' W ANNUALLY

INDEX TO ADJOINING MAPS

093F091	093F092	093F093
093F081	<b>093F082</b>	093F083
093F071	093F072	093F073

1000 m 0 1 km

ORIGINAL PRODUCED AT 1: 20 000

LAST MAP UPDATE: 2004 MAY 7

Version Number: 0001

**BRITISH COLUMBIA**

MINISTRY OF ENERGY AND MINES

MINISTRY OF SUSTAINABLE RESOURCE MANAGEMENT

**MINERAL TITLES REFERENCE MAP**

**M093F082**

North American Datum - 1983


U.T.M. Coordinate System - Zone 10

Compilation Date: 2004 MAY 07



# Uncha Lake

## Day Claims 1 to 8



Claim #	Tenure #
1	408048
2	408049
3	408050
4	408051
5	408052
6	408053
7	408054
8	408055

NTS Map Sheet 93F/13E

MINE  
R

Innovative Energy Inc.  
GEOLOGICAL SURVEY BRANCH  
ASSESSMENT  
Uncha Lake Perlite  
Claim Map  
Day Claims

27